

March 15, 2007

**HEAT-KIT(tm) CONTRAFLOW HEATER SYSTEM  
PRICING**

---

COMPLETE HEAT-KIT CORE, **ready for facing**

---

**HEATKIT Contraflow Heater Core with 22" firebox:**

Delivered to your site and installed onto your foundation

Includes delivery within 300 miles of Ottawa.

Price includes hardware (doors, dampers, etc.) and firebricks.

6500.00

**OPTIONS:**

**Retained Heat White Bakeoven** in upper chamber, front or rear

Includes cast iron bakeoven door w. ceramic glass

975.00

**Domestic Hot Water Coil**, single loop

3/4" i.d. Schedule 40 boiler tubing, 304 stainless steel w. pipe thread

Installed in core, permissions and hookup by others

250.00

**Slab on Grade Installation** (requires ashbox door with air control)

100.00

**Setup for heated benches**

Cost varies with design

Please ask for a quote

**Customized cores**

Corner heater (45 degree sidewalls)

add 400.00

Top exit, see through, curved or angled side walls,

extra height, etc.

Please ask for a quote

---

**PLEASE NOTE** that the following are **not** included in the core cost:

---

- Masonry facing for core, installed by your local mason
- Foundation
- Chimney (a masonry chimney is recommended for the first 8 feet)
- Extra travel over 300 miles
- 5% G.S.T. - 7.5% Q.S.T. (Québec only)

**Design Consulting:**


Send us your plans or a sketch of your layout and we will send you the appropriate foundation drawings. Two hours of design time is included in the cost of the core. For custom designs, please ask for a quote. Additional design time is billed at 50.00/hr.


There is no charge for telephone consulting with your mason during finishing.

**Payment and Scheduling Terms:**

50% Deposit with order to schedule job.

Founding Member





**Masonry Stove  
Builders**

RR 5 Shawville Québec J0X 2Y0

**Energy Solutions**

Balance upon installation.Voice  
819.647.5092  
Fax 819.647.6082  
[mheat@mha-net.org](mailto:mheat@mha-net.org)  
[www.heatkit.com](http://www.heatkit.com)

June 27, 2008

## **HEAT-KIT(tm) CONTRAFLOW HEATER SYSTEM**

### ***PRICING***

---

#### **HEAT-KIT CORE, **for self assembly****

---

To evaluate this option, ask for assembly instructions for specific model. Assembly instructions can be downloaded from our web site at: [www.mha-net.org/msb/assy-hk.htm](http://www.mha-net.org/msb/assy-hk.htm)

#### **HEATKIT Contraflow Heater Core with 22" firebox:**

Components including hardware  
Does not include firebricks (see below) 4750.00

#### **OPTIONS:**

**Retained Heat White Bakeoven** in upper chamber, front or rear. 27"x15"  
Includes cast iron bakeoven door w. ceramic glass 950.00

**Domestic Hot Water Coil**, single loop  
3/4" i.d. Schedule 40 boiler tubing, 304 stainless steel w. pipe thread  
Installed in core, permissions and hookup by others 225.00

**Slab on Grade Installation** (requires ashbox door with air control) 125.00

#### **Customized cores**

Corner heater (45 degree sidewalls) add 400.00

Top exit, see through, curved or custom sidewalls,  
extra height, etc. Please ask for a quote

#### **Setup for heated benches**

No extra components required from us. Built from local  
materials. See note on additional design time, below. Please ask for a quote

---

**PLEASE NOTE** that the following are **not** included in the core cost:

---

- 230 standard firebricks (200 with oven), available locally
- 20 split firebricks, 30 common bricks, 2 bags mortar mix, available locally
- Shipping. Cost to palletize and deliver to Ottawa freight terminal is 125.00. Ask for a shipping quote from Ottawa to you. Shipped freight collect.
- 5% G.S.T. - 7.5% Q.S.T. (Québec only)

#### **Design Consulting:**

Send us your plans or a sketch of your layout and we will send you the appropriate foundation drawings. One hour of design time is included in the cost of the core. For custom designs, please ask for a quote. Additional design time is billed at 50.00/hr. There is no charge for telephone consulting during construction.

#### **Payment and Scheduling Terms:**

50% Deposit with order to schedule job.  
Balance upon receipt of components.