

August 9, 2009

HEAT-KIT(tm) CONTRAFLOW HEATER SYSTEM

PRICING

HEAT-KIT CORE, **for self assembly**

To evaluate this option, ask for assembly instructions for specific model. Assembly instructions can be downloaded from our web site at: heatkit.com/html/assy-hk.htm

HEATKIT Contraflow Heater Core with 22" firebox:

Components including hardware
Does not include firebricks (see below) 5450.00

OPTIONS:

Retained Heat White Bakeoven in upper chamber, front or rear. 27"x15"
Includes cast iron bakeoven door w. ceramic glass 950.00

Domestic Hot Water Coil, single loop
3/4" i.d. Schedule 40 boiler tubing, 304 stainless steel w. pipe thread
Installed in core, permissions and hookup by others 225.00

Slab on Grade Installation (requires ashbox door with air control) 125.00

Customized cores

Corner heater (45 degree sidewalls) add 450.00

Top exit, see through, curved or custom sidewalls,
extra height, etc. Please ask for a quote

Setup for heated benches

No extra components required from us. Built from local
materials. See note on additional design time, below. Please ask for a quote

PLEASE NOTE that the following are **not** included in the core cost:


- 240 standard firebricks (200 with oven), available locally
- 20 split firebricks, 30 common bricks, 2 bags mortar mix, available locally
- Shipping. Cost to palletize and deliver to Ottawa freight terminal is 125.00. Ask for a shipping quote from Ottawa to you. Shipped freight collect.
- 5% G.S.T. - 7.5% Q.S.T. (Québec only)


Design Consulting:

Send us your plans or a sketch of your layout and we will send you the appropriate foundation drawings. One hour of design time is included in the cost of the core. For custom designs, please ask for a quote. Additional design time is billed at 75.00/hr. There is no charge for telephone consulting during construction.

Payment and Scheduling Terms:

50% Deposit with order to schedule job.
Balance upon receipt of components.





Masonry Stove Builders

25 Brouse Road, RR 5 Shawville Québec J0X 2Y0

Voice 819.647.5092
Fax 819.647.6082
mheat@heatkit.com
www.heatkit.com

August 9, 2009

HEAT-KIT(tm) CONTRAFLOW HEATER SYSTEM

PRICING

COMPLETE HEAT-KIT CORE, **ready for facing**

HEATKIT Contraflow Heater Core with 22" firebox:

Delivered to your site and installed onto your foundation

Includes delivery within 300 miles of Ottawa.

Price includes hardware (doors, dampers, etc.) and firebricks. 7100.00

OPTIONS:

Retained Heat White Bakeoven in upper chamber, front or rear

Includes cast iron bakeoven door w. ceramic glass

975.00

Domestic Hot Water Coil, single loop

3/4" i.d. Shedule 40 boiler tubing, 304 stainless steel w. pipe thread

Installed in core, permissions and hookup by others

250.00

Slab on Grade Installation (requires ashbox door with air control)

125.00

Setup for heated benches

Cost varies with design

Please ask for a quote

Customized cores

Corner heater (45 degree sidewalls)

add 450.00

Top exit, see through, curved or angled side walls,
extra height, etc.

Please ask for a quote

PLEASE NOTE that the following are **not** included in the core cost:

- Masonry facing for core, installed by your local mason
- Foundation
- Chimney (a masonry chimney is recommended for the first 8 feet)
- Extra travel over 300 miles
- 5% G.S.T. - 7.5% Q.S.T. (Québec only)

Design Consulting:

Send us your plans or a sketch of your layout and we will send you the appropriate foundation drawings. Two hours of design time is included in the cost of the core. For custom designs, please ask for a quote. Additional design time is billed at 50.00/hr. There is no charge for telephone consulting with your mason during finishing.

Payment and Scheduling Terms:

50% Deposit with order to schedule job.